



TYPICAL SECTION

NOTES:

1. Pipe diameter shall be 4 inches or greater. See specifications for acceptable materials.
2. Pipes stubbed out for future building connections shall be plugged with a fitting approved by the manufacturer.
3. Maximum distance between cleanouts shall be 100 feet. The maximum aggregate change in direction between cleanouts shall be 135°. Construct additional cleanouts as necessary.
4. A water service and a sewer service may be placed in the same trench if the water service is placed on an undisturbed earth shelf 12 inches (min) above the side sewer.
5. Abandoned sewer services shall be plugged within 5 feet of the property line with a fitting approved by the manufacturer or a minimum 2-foot long poured concrete plug.
6. Pipe material shall be PVC SDR 35 unless otherwise approved by the city inspector.

dwc 3-00
DRR

P:\Engr & CAD\STANDARD DWGS - ALL YEARS\Std Dwgs 2014\Side Sewer Installation 24.dwg

**SIDE SEWER INSTALLATION
(Storm and Sanitary Sewer)**

PAGE NO:

24